

Summary of Bid Document Updates 5/12/26

Added Item 021 Crushed Rock and Item 022 Boulders to the Bid Sheet and provided a description of the tasks in the Scope of Work in the draft Construction Services Agreement.

Updated Item Description

021 – Crushed Rock: The Contractor will procure, transport, deliver and spread 150 tons of crushed top-course rock in the driveway/parking lot of the Headwaters Bar and Restaurant located at 21328 WA-207, Leavenworth, WA 98826.

022 –Boulders: The Contractor will opportunistically salvage four boulders during construction of the Area G Side Channel or Engineered Large Wood Structures. The Contractor will transport the boulders to the Yakama Nation's Natapoc Property (47.806631, -120.697096) and place them so as to discourage motorized vehicles from circumventing the gate.

The engineered design for Chiwawa Area G Phase 2 Large Wood Project currently illustrates installation of a cofferdam and excavation of a scour pool associated with B2 and B4. We are updating the design to eliminate the cofferdam and scour pool associated with both of these structures. A note to this effect has been added to Sheet 9 in the engineered design.